

## NOTES

- ① MANHOLE COVER SHALL CONFORM TO MN/DOT S.P. 4020 J.
- ② MANHOLE BASE SHALL CONFORM TO MN/DOT S.P. 4011 E.
- ③ REFER TO PLANS AND S.D.P. 1-11 FOR CASTING REQUIRED. CASTING SHALL BE BOLTED TO CONCRETE IN FIELD APPLICATIONS.
- ④ ADJUSTING RINGS SHALL BE PER S.D.P. 1-12, AND BE FULLY MORTARED.
5. STRUCTURE SHALL BE PRECAST CONCRETE.
- ⑥ REINFORCING SHALL BE A MINIMUM OF A SINGLE LINE STEEL WIRE FABRIC HAVING AN AREA OF NOT LESS THAN 0.12 SQ. IN. PER FOOT IN EACH DIRECTION.
- ⑦ STEPS ARE SPACED AT 16" O.C. MAX. AND SHALL CONFORM TO MN/DOT S.P. 4180 J. STEPS SHALL BE ORIENTED ON THE UPSTREAM LEFT SIDE.
- ⑧ ALL JOINTS TO BE GASKETED. REFER TO MN/DOT SPEC. 3726.
- ⑨ PROVIDE CONCRETE FILLETS TO FIT BOTTOM PORTION OF PIPE TO DIRECT FLOW TO OUTLET AT 1/4" PER FT. MINIMUM SLOPE. MINIMUM CONCRETE THICKNESS AT LOWEST INVERT SHALL BE 1 1/2".
- ⑩ WATERTIGHT SEAL PER MN/DOT S.P. 4007 C. REQUIRED FOR SANITARY SEWER USE.

DEPARTMENT OF PUBLIC WORKS  
CITY OF ROCHESTER, MINNESOTA


## STRUCTURE TYPE 4 (XX in.)

*Donald Nelson*  
ASST. CITY ENGINEER


*Paul W. Finner*  
DIRECTOR

SEE SHEET 2 FOR MANHOLE DIMENSIONS

SHT 1 OF 2 SHTS	DATE REVISED 6/15/07	PLATE NO. 1-04	REV. G
-----------------	-------------------------	-------------------	-----------



MANHOLE TOP SLAB



ALTERNATE TOP  
SLAB FOR MANHOLE

MH TOP SLAB				MANHOLE DIMENSIONS					MAX. PIPE SIZE	
W	X	Y	Z	A	B	C	D	E	135'-180'	90'
6"	9"	-	58"	48"	5"	64"	6"	6"	27"	18"
6"	6"	-	65"	54"	5.5"	72"	8"	8"	33"	21"
7"	3"	-	72"	60"	6"	78"	8"	8"	36"	24"
7"	0"	-	79"	66"	6.5"	85"	8"	8"	42"	30"
8"	-	3"	86"	72"	7"	92"	8"	8"	42"	33"
8"	-	6"	93"	78"	7.5"	100"	8"	8"	48"	36"
9"	-	9"	100"	84"	8"	106"	8"	8"	54"	42"
9"	-	12"	107"	90"	8.5"	114"	8"	8"	60"	42"
9"	-	15"	114"	96"	9"	120"	8"	8"	60"	42"
9"	-	18"	121"	102"	9.5"	127"	8"	8"	60"	48"
10"	-	21"	126"	108"	10"	132"	9"	12"	60"	54"
11"	-	24"	140"	120"	10"	146"	12"	12"	60"	60"

DEPARTMENT OF PUBLIC WORKS  
CITY OF ROCHESTER, MINNESOTA  
**STRUCTURE TYPE 4 (XX in.)  
MANHOLE DIMENSIONS**

*Donald Nelson*  
ASST. CITY ENGINEER

*Paul W. Finner*  
DIRECTOR

SHT 2 OF 2 SHTS

DATE REVISED  
3/22/06

PLATE NO.  
1-04

REV.  
A